BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Constructions of CC roads and drains at LBS Nagara in Ward No.04

Agency:-R.Subramani

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of R.Subramani		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
1	227.7	Removing BS Slab of drain and Stacking and as per the direction of engineer in charge of work	sqm	69.12	Rupees Sixty Nine And Paise Twelve Only
2	227.7	Refixing Stone Slabs of drains and Pointing in C.M(1:3). and as per the direction of engineer in charge of work	sqm	84.56	Rupees Eighty Four And Paise Fifty Six Only
3	75.9	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5cm thick and as per the direction of engineer in charge of work	sqm	698.25	Rupees Six Hundred Ninety Eight And Paise Twenty Five Only
4	556.6	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. and as per the direction of engineer in charge of work	cum	91.93	Rupees Ninety One And Paise Ninety Three Only
5	556.6	Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M and as per the direction of engineer in charge of work	cum	89.56	Rupees Eighty Nine And Paise Fifty Six Only
6	154.5	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification and as per the direction of engineer in charge of work	cum	5616.17	Rupees Five Thousand Six Hundred Sixteen And Paise Seventeen Only
7	231.15	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification and as per the direction of engineer in charge of work	cum	336.12	Rupees Three Hundred Thirty Six And Paise Twelve Only
8	154.5	Construction of granular sub-base by providing close graded material, crushed stone aggregates of granite/trap/basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material and as per the direction of engineer in charge of work	cum	1748.89	Rupees One Thousand Seven Hundred Forty Eight And Paise Eighty Nine Only

Contractor

Executive Engineer,
Project Division

18/12

Sl No	App Qty	Description of work	Approved Rates of R.Subramani		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
9	154.5	cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2M20/M30 at 380/450 kg per cum, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including leveling the form work as per drawing,), spreading the concrete with shovels, rackers compacted using needle, scred and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grade as per drawing complete as per specification M30(at 360kg per cum coarse aggregate @ 0.69cum and fine aggregare @ 0.46cum),	cum	6527.78	*Rupees Six Thousand Five Hundred Twenty Seven And Paise Seventy Eight Only*
10	1545	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift. and as per the direction of engineer in charge of work	sqm	100.12	*Rupees One Hundred And Paise Twelve Only*
11	435	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement. and as per the direction of engineer in charge of work	Rmt	127.9	*Rupees One Hundred Twenty Seven And Paise Ninety Only*

18/12/17

Contractor

Executive Engineer,
Project Division